

Systeemvloeren in gewapend beton

Rector vloeren

Uitvoering:

Ruwe onderzijde

Ribben in voorgespannen beton

Vulpotten in beton

Rf (min) 30

Hoogte (mm) 120

Breedte (mm) 500

Meting: m²

Overspanning (cm)	450	500	550	600	650	700	750	800	850
Materieel	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57
Vulbeton: stortbak	1,66	1,66	1,65	1,65	1,64	1,64	1,64	1,63	1,63
Welfsels	23,38	24,55	25,78	27,07	28,42	29,84	31,34	32,90	34,55
Arbeid	27,18	26,91	26,64	26,38	26,12	25,86	25,60	25,35	25,10
Calculatienorm arbeid	0,639	0,633	0,627	0,621	0,614	0,608	0,602	0,596	0,591
Totaal	52,80	53,69	54,65	55,67	56,76	57,92	59,15	60,46	61,85

Hoogte (mm) 160

Breedte (mm) 500

Meting: m²

Overspanning (cm)	450	500	550	600	650	700	750	800	850
Materieel	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57
Vulbeton: stortbak	3,16	3,15	3,14	3,13	3,13	3,12	3,11	3,10	3,09
Welfsels	24,55	25,78	27,07	28,42	29,84	31,34	32,90	34,55	36,28
Arbeid	27,45	27,18	26,91	26,64	26,38	26,12	25,86	25,60	25,35
Calculatienorm arbeid	0,646	0,639	0,633	0,627	0,621	0,614	0,608	0,602	0,596
Totaal	55,73	56,68	57,69	58,77	59,92	61,14	62,44	63,83	65,29

Hoogte (mm) 200

Breedte (mm) 500

Meting: m²

Overspanning (cm)	450	500	550	600	650	700	750	800	850
Materieel	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57
Vulbeton: stortbak	5,46	5,44	5,43	5,41	5,40	5,39	5,37	5,36	5,35
Welfsels	25,78	27,07	28,42	29,84	31,34	32,90	34,55	36,28	38,09
Arbeid	28,00	27,72	27,45	27,18	26,91	26,64	26,38	26,12	25,86
Calculatienorm arbeid	0,659	0,652	0,646	0,639	0,633	0,627	0,621	0,614	0,608
Totaal	59,81	60,81	61,87	63,01	64,22	65,50	66,87	68,32	69,87

© ASPEN INDEX

Tel 03 281 33 68

Fax 03 230 58 54

476

Nieuwbouw
jan/08

41


Predallen

getrild beton C25-30

Breedte (cm) 120

Dikte (mm) 50

Onderzijde met gratenraster



Overspanning (cm)

	200	250	300	350	400	450	500	550	600
Materieel	1,16	1,16	1,16	1,16	1,16	1,16	1,16	1,16	1,16
Materiaal	19,22	20,18	21,18	22,24	23,36	24,52	25,75	27,04	28,39
Arbeid	28,54	27,85	27,17	26,50	25,86	25,23	24,61	24,01	23,43
Calculatienorm arbeid	0,672	0,655	0,639	0,624	0,608	0,594	0,579	0,565	0,551
Totaal	48,92	49,19	49,52	49,91	50,38	50,92	51,53	52,21	52,98

8 (23.4) G g2

Systeemvloeren in gebakken klei

Uitvoering:

Ruwe onderzijde

Ribben in voorgespannen beton

Vulpotten in gebakken klei

Hoogte (mm) 120

Breedte (mm) 500

Meting: m²

Overspanning (cm)

	450	500	550	600	650	700	750	800	850
Materieel	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57
Vulbeton Stortbak	2,66	2,65	2,65	2,64	2,63	2,63	2,62	2,61	2,61
Welfsels	19,80	20,79	21,83	22,92	24,07	25,27	26,54	27,87	29,26
Arbeid	27,18	26,91	26,64	26,38	26,12	25,86	25,60	25,35	25,10
Calculatienorm arbeid	0,639	0,633	0,627	0,621	0,614	0,608	0,602	0,596	0,591
Totaal	50,21	50,93	51,69	52,52	53,39	54,33	55,33	56,40	57,54

Hoogte (mm) 150

Breedte (mm) 500

Meting: m²

Overspanning (cm)

	450	500	550	600	650	700	750	800	850
Materieel	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57	0,57
Vulbeton: stortbak	3,99	3,98	3,97	3,96	3,95	3,94	3,93	3,92	3,91
Welfsels	25,25	26,52	27,84	29,23	30,70	32,23	33,84	35,53	37,31
Arbeid	27,45	27,18	26,91	26,64	26,38	26,12	25,86	25,60	25,35
Calculatienorm arbeid	0,646	0,639	0,633	0,627	0,621	0,614	0,608	0,602	0,596
Totaal	57,26	58,25	59,29	60,41	61,60	62,86	64,20	65,63	67,14

© ASPEN INDEX

Tel 03 281 33 68

Fax 03 230 58 54

477

Nieuwbouw
jan/08

41